Bruhat Bangalore Mahanagara Palike
Excecutive Engineer Yelahanka Project Division

Name of Work:Modified Estimation for 1.Construction of Kempegowda Statue at Yelahanka Mini Vidhanasoudha in Kempegowda Ward No.01 of Yelahanka sub division 2. Providing and fixing stone benches to the parks in Kempegowda ward No.01 of Yelahanka sub division 3.Development of Parks comes under Attur Ward No.03 4. Fixing Stone benches to park comes under Attur Ward No.03

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
1	KSRB 2-2: Earth work Excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc., either in pits or trenches 1.5m and above in width, in soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches stacking the excavated soil clear from edges of excavation with lead upto 50m. including breaking of clods complete as per specifications.								
	Sir M. Vishveshwaraya Park								
	South	1	48.80	0.80	0.80	31.23			
	West	1	83.10	0.80	0.80	53.18			
	North	1	84.90	0.80	0.80	54.34			
	East	1	69.5	0.80	0.80	44.48			
	In Between Fencing	1	53.00	0.80	0.80	33.92			
	Tree Gap	-4	1.00	0.80	0.80	-2.56			
	Inside Mini Vidhanasoudha								
	Parking Area	1	38.40	12.90	0.25	123.84			
	Pathway-Left Hand Side	1	66.50	1.70	0.25	28.26			
	Pathway-Right Hand Side	1	35.60	1.70	0.25	15.13			
		1	5.90	0.90	0.25	1.33			
	Building Front	1	9.00	2.10	0.25	4.73			
		1	8.20	1.10	0.25	2.26			
		1	7.70	1.40	0.25	2.70			
	Entrance Main Gate	1	13.40	10.20	0.25	34.17			
	New Kerb								
	Childrens Play Area	2	22.70	0.20	0.20	1.82			
	Debris	1	30.00	4.00	0.40	48.00			
		1	30.00	3.50	0.30	31.50			
		1	30.00	3.60	0.30	32.40			
	Culvert	1	10.30	0.90	0.80	7.42			
	Benches Platform								
	Ward No:03								
	Duo Marvel Layout								
	Near Main Gate	1	2.10	1.50	0.30	0.95			
	Layout Association	3	2.10	1.50	0.30	2.84			
	1st Cross (Opp Kempton Appt)	2	2.10	1.20	0.30	1.51			
	Opp Kempegowda Hall	4	2.10	1.20	0.30	3.02			
	Near Vinayaka Temple	4	2.10	1.20	0.30	3.02			
	Park	10	2.10	1.50	0.30	9.45			
	Anantapur Government school								
	School Premises	2	5.20	1.50	0.30	4.68			
	Attur								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Lake Premises	25	2.10	1.50	0.30	23.63			
	Vishwanagar								
	B Block	1	1.80	1.50	0.30	0.81			
	1st cross road at dead end	1	1.95	2.00	0.30	1.17			
	1st cross road	1	2.00	1.45	0.30	0.87			
	2nd cross road	6	1.80	1.20	0.30	3.89			
	Main Road near D Block	2	1.80	1.50	0.30	1.62			
	Main Road near Karnataka pole	2	1.80	1.10	0.30	1.19			
	AMS Extension								
	1st cross road	6	2.10	1.20	0.30	4.54			
	4th main road	1	2.10	1.10	0.30	0.69			
	3rd main road	2	2.10	1.20	0.30	1.51			
	Near Karnataka pole	1	0.00	0.00	0.00	0.00			
	Dairy Circle								
	Near Help point	1	1.80	1.40	0.30	0.76			
		1	2.60	0.90	0.30	0.70			
	Valmiki Park	20	2.00	1.45	0.30	17.40			
	Kittur Rani Chennamma Park	10	2.10	1.50	0.30	9.45			
	Sardar Vallabhai Patel Park	10	2.10	1.50	0.30	9.45			
	BM Srikantaiah Park	10	2.00	1.70	0.30	10.20			
	Panchakshari Gavayi Park	6	2.10	1.40	0.30	5.29			
	Vivekananda Park	10	2.10	1.47	0.30	9.26			
	CV Raman Park	5	2.10	1.50	0.30	4.73			
	Abdul Kalam Park	5	2.10	1.44	0.30	4.54			
	Visvesvaraya Park	13	2.10	1.52	0.30	12.45			
	Temple premises	1	2.10	1.50	0.30	0.95			
		1	3.60	1.50	0.30	1.62			
		1	5.70	1.50	0.30	2.57			
	Dara Bendre Park	5	2.10	1.50	0.30	4.73			
	Ramana Maharshi Park	2	2.10	1.50	0.30	1.89			
		1	3.60	1.50	0.30	1.62			
	Kuvempu Park	9	2.15	1.65	0.30	9.58			
	Ward no 01								
	Maruthinagara								
	Opp To BWSSB	1	4.70	1.20	0.30	1.69			
		8	2.10	1.20	0.30	6.05			
	Near BWSSB	1	3.60	1.50	0.30	1.62			
	Maruthi Nagara 2nd Stage	2	2.10	1.20	0.30	1.51			
		1	3.60	1.20	0.30	1.30			
		4	2.10	1.20	0.30	3.02			
	Vikas Layout								
	1st Main Rd	3	2.10	1.20	0.30	2.27			
	3rd Main Rd	4	2.10	1.20	0.30	3.02			
	3rd Cross Rd	4	2.10	1.20	0.30	3.02			
	2nd Cross Rd	4	2.10	1.20	0.30	3.02			
	Main Road	5	2.10	1.20	0.30	3.78			
	2nd Cross Rd(Vivekanda Rd)	3	2.10	1.20	0.30	2.27			
		2	5.40	1.20	0.30	3.89			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	nd Main Rd Upto 4th Cross Rd	3	2.10	1.20	0.30	2.27			
	Cross Rd	2	2.10	1.20	0.30	1.51			
	4th Cross Rd	1	3.60	1.20	0.30	1.30			
	Balazi Layout								
	Main Road	5	2.10	1.20	0.30	3.78			
	3rd Cross Rd LHS Side	4	2.10	1.20	0.30	3.02			
	3rd Cross Rd RHS Side	7	2.10	1.20	0.30	5.29			
	Near School Rd	2	2.10	1.20	0.30	1.51			
	Ward Member Vishwa House	2	2.10	1.20	0.30	1.51			
	Near Cambridge School (SIR-M-V Rd)	3	2.10	1.20	0.30	2.27			
	Cross Rd	1	2.10	1.20	0.30	0.76			
	Cross Rd-1	2	2.10	1.20	0.30	1.51			
	Shivanahalli (Jakkur Layout)								
		1	3.60	1.20	0.30	1.30			
	Shivanahalli Main Rd								
		1	2.10	1.40	0.30	0.88			
		2	2.10	1.20	0.30	1.51			
	Cross Rd-2	2	2.10	1.20	0.30	1.51			
	Cricket Club Rd	1	3.60	1.20	0.30	1.30			
	Anjaneya Swamy Temple Rd	4	2.10	1.20	0.30	3.02			
	Krushi University Employee Union Rd	3	3.60	1.20	0.30	3.89			
	Sky Blue Appartment	2	2.10	1.20	0.30	1.51			
	Sri Nikethana #133	2	3.60	1.20	0.30	2.59			
	inside Post Office								
		1	12.50	1.80	0.30	6.75			
	Deduct Tree Guards	-2	0.60	0.60	0.30	-0.22			
		1	3.90	1.50	0.30	1.76			
		1	3.60	1.40	0.30	1.51			
	Inside Mini Vidhanasoudha								
	Infront Kempegowda Statue	4	2.50	1.80	0.30	5.40			
	Back Side Kempegowda Statue	2	2.50	1.80	0.30	2.70			
	Ashok Pillar Back Side	2	2.50	1.80	0.30	2.70			
	Infront of Ganesha Temple	2	2.15	1.65	0.30	2.13			
	Ambedkar Park								
	Northern Side	1	86.00	1.00	0.90	77.40			
	Eastern Side	1	13.50	1.00	0.90	12.15			
	New Kerb								
	Ambedkar Park								
	Eastern Side	1	115.90	0.20	0.20	4.64			
	NIPCCD Staff Quarters(Blind School Park)								
	Southern Side	1	36.90	0.20	0.20	1.48			
	Box-A								
		1	2.80	0.20	0.20	0.11			
		1	2.70	0.20	0.20	0.11			
	Box-B and Box-C								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
		3	2.90	0.20	0.20	0.35			
		1	12.30	0.20	0.20	0.49			
	Box-D								
		2	3.70	0.20	0.20	0.30			
		1	3.20	0.20	0.20	0.13			
	Box-E								
		1	3.20	0.20	0.20	0.13			
		1	3.40	0.20	0.20	0.14			
		1	2.00	0.20	0.20	0.08			
	Loose Soil/ Debris								
	Ambedkar Park								
		1	30.00	7.00	0.70	147.00			
		1	30.00	6.80	0.60	122.40			
		1	30.00	6.50	0.55	107.25			
		1	25.40	6.20	0.50	78.74			
	NIPCCD Staff Quarters(Blind School Park) Inner Play Area								
		1	30.00	8.20	0.60	147.60			
		1	7.00	8.10	0.50	28.35			
	NIPCCD Staff Quarters(Blind School Park) Outer								
		1	30.00	5.50	0.60	99.00			
		1	7.00	5.40	0.55	20.79			
						1670.74	**Cum**		
			Upto 125%			**1255.29**	**Cum**	**398.40**	**500106.54**
			Above 125%			**415.45**	**Cum**	**398.40**	**165515.70**
	Approved Rate	398.40							
2	KSRR M2100-10. Providing and laying plain cement concrete of mix 1:3:6 with opc @ 220kgs, with crushed 40mm and down side Graded grainte metal coarse aggregates @0.89Cum and fine aggregates @ 0.46Cum in foundation Mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all m,aterials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.								
	Sir M. Vishveshwaraya Park								
	South	1	48.80	0.80	0.15	5.86			
	West	1	83.10	0.80	0.15	9.97			
	North	1	84.90	0.80	0.15	10.19			
	East	1	69.50	0.80	0.15	8.34			
	In Between Fencing	1	53.00	0.80	0.15	6.36			
	Tree Gap	-4	1.00	0.80	0.15	-0.48			
	Cobble Stone Resetting								
	Sir M. Vishveshwaraya Park								
	Southern Side	1	155.50	3.68	0.15	85.84			
	Missing/Damaged Kerb								
	Sir M. Vishveshwaraya Park	1	71.00	0.20	0.10	1.42			
	New Kerb								
	Childrens Play Area	2	22.70	0.20	0.10	0.91			
	Culvert	1	10.30	0.90	0.15	1.39			
	Benches Platform								
	Ward No:03								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Duo Marvel Layout								
	Near Main Gate	1	2.10	1.50	0.15	0.47			
	Layout Association	3	2.10	1.50	0.15	1.42			
	1st Cross (Opp Kempton Appt)	2	2.10	1.20	0.15	0.76			
	Opp Kempegowda Hall	4	2.10	1.20	0.15	1.51			
	Near Vinayaka Temple	4	2.10	1.20	0.15	1.51			
	Park	10	2.10	1.50	0.15	4.73			
	Anantapur Government school								
	School Premises	2	5.20	1.50	0.15	2.34			
	Attur								
	Lake Premises	25	2.10	1.50	0.15	11.81			
	Vishwanagar								
	B Block	1	1.80	1.50	0.15	0.41			
	1st cross road at dead end	1	1.95	2.00	0.15	0.59			
	1st cross road	1	2.00	1.45	0.15	0.44			
	2nd cross road	6	1.80	1.20	0.15	1.94			
	Main Road near D Block	2	1.80	1.50	0.15	0.81			
	Main Road near Karnataka pole	2	1.80	1.10	0.15	0.59			
	AMS Extension								
	1st cross road	6	2.10	1.20	0.15	2.27			
	4th main road	1	2.10	1.10	0.15	0.35			
	3rd main road	2	2.10	1.20	0.15	0.76			
	Near Karnataka pole	1	0.00	0.00	0.15	0.00			
	Dairy Circle								
	Near Help point	1	1.80	1.40	0.15	0.38			
		1	2.60	0.90	0.15	0.35			
	Valmiki Park	20	2.00	1.45	0.15	8.70			
	Kittur Rani Chennamma Park	10	2.10	1.50	0.15	4.73			
	Sardar Vallabhai Patel Park	10	2.10	1.50	0.15	4.73			
	BM Srikantaiah Park	10	2.00	1.70	0.15	5.10			
	Panchakshari Gavayi Park	6	2.10	1.40	0.15	2.65			
	Vivekananda Park	10	2.10	1.48	0.15	4.66			
	CV Raman Park	5	2.10	1.50	0.15	2.36			
	Abdul Kalam Park	5	2.10	1.45	0.15	2.28			
	Viswesvaraya Park	13	2.10	1.52	0.15	6.22			
	Temple premises	1	2.10	1.50	0.15	0.47			
		1	3.60	1.50	0.15	0.81			
		1	5.70	1.50	0.15	1.28			
	Dara Bendre Park	5	2.10	1.50	0.15	2.36			
	Ramana Maharshi Park	2	2.10	1.50	0.15	0.95			
		1	3.60	1.50	0.15	0.81			
	Kuvempu Park	9	2.15	1.63	0.15	4.73			
	Ward no 01								
	Maruthinagara								
	Opp To BWSSB	1	4.70	1.20	0.15	0.85			
		8	2.10	1.20	0.15	3.02			
	Near BWSSB	1	3.60	1.50	0.15	0.81			
	Maruthi Nagara 2nd Stage	2	2.10	1.20	0.15	0.76			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
		1	3.60	1.20	0.15	0.65			
		4	2.10	1.20	0.15	1.51			
	Vikas Layout								
	1st Main Rd	3	2.10	1.20	0.15	1.13			
	3rd Main Rd	4	2.10	1.20	0.15	1.51			
	3rd Cross Rd	4	2.10	1.20	0.15	1.51			
	2nd Cross Rd	4	2.10	1.20	0.15	1.51			
	Main Road	5	2.10	1.20	0.15	1.89			
	2nd Cross Rd(Vivekanda Rd)	3	2.10	1.20	0.15	1.13			
		2	5.40	1.20	0.15	1.94			
	2nd Main Rd Upto 4th Cross Rd	3	2.10	1.20	0.15	1.13			
	Cross Rd	2	2.10	1.20	0.15	0.76			
	4th Cross Rd	1	3.60	1.20	0.15	0.65			
	Balazi Layout								
	Main Road	5	2.10	1.20	0.15	1.89			
	3rd Cross Rd LHS Side	4	2.10	1.20	0.15	1.51			
	3rd Cross Rd RHS Side	7	2.10	1.20	0.15	2.65			
	Near School Rd	2	2.10	1.20	0.15	0.76			
	Ward Member Vishwa House	2	2.10	1.20	0.15	0.76			
	Near Cambridge School (SIR-M-V Rd)	3	2.10	1.20	0.15	1.13			
	Cross Rd	1	2.10	1.20	0.15	0.38			
	Cross Rd-1	2	2.10	1.20	0.15	0.76			
	Shivanahalli (Jakkur Layout)								
		1	3.60	1.20	0.15	0.65			
	Shivanahalli Main Rd								
		1	2.10	1.40	0.15	0.44			
		2	2.10	1.20	0.15	0.76			
	Cross Rd-2	2	2.10	1.20	0.15	0.76			
	Cricket Club Rd	1	3.60	1.20	0.15	0.65			
	Anjaneya Swamy Temple Rd	4	2.10	1.20	0.15	1.51			
	Krushi University Employee Union Rd	3	3.60	1.20	0.15	1.94			
	Sky Blue Appartment	2	2.10	1.20	0.15	0.76			
	Sri Nikethana #133	2	3.90	1.20	0.15	1.40			
	Inside Post Office								
		1	12.50	1.80	0.15	3.38			
	Deduct Tree Guards	-2	0.60	0.60	0.15	-0.11			
		1	3.90	1.50	0.15	0.88			
		1	3.60	1.40	0.15	0.76			
	Inside Mini Vidhanasoudha								
	Infront Kempegowda Statue	4	2.50	1.80	0.15	2.70			
	Back Side Kempegowda Statue	2	2.50	1.80	0.15	1.35			
	Ashok Pillar Back Side	2	2.50	1.80	0.15	1.35			
	Infront of Ganesha Temple	2	2.45	1.65	0.15	1.21			
	For Kerbs Benches Platform surround								
	Ward No:03								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Duo Marvel Layout								
	Anantapur Government school								
	School Premises	2	14.40	0.20	0.10	0.58			
	Attur								
	Lake Premises	25	7.20	0.20	0.10	3.60			
	Vishwanagar								
	B Block	1	6.60	0.20	0.10	0.13			
	1st cross road at dead end	1	7.90	0.20	0.10	0.16			
	1st cross road	1	6.90	0.20	0.10	0.14			
	2nd cross road	6	6.00	0.20	0.10	0.72			
	Main Road near D Block	2	6.60	0.20	0.10	0.26			
	Main Road near Karnataka pole	2	5.80	0.20	0.10	0.23			
	AMS Extension								
	1st cross road	6	4.50	0.20	0.10	0.54			
	4th main road	1	4.30	0.20	0.10	0.09			
	3rd main road	2	4.50	0.20	0.10	0.18			
	Dairy Circle								
	Near Help point	1	3.70	0.20	0.10	0.07			
		1	7.60	0.20	0.10	0.15			
	Valmiki Park								
		3	6.80	0.20	0.10	0.41			
		2	7.20	0.20	0.10	0.29			
		1	6.60	0.20	0.10	0.13			
		2	7.20	0.20	0.10	0.29			
		10	6.80	0.20	0.10	1.36			
	Kittur Rani Chennamma Park								
		10	7.20	0.20	0.10	1.44			
	Sardar Vallabhai Patel Park								
		10	7.20	0.20	0.10	1.44			
	BM Srikantaiah Park								
		8	7.20	0.20	0.10	1.15			
		2	8.40	0.20	0.10	0.34			
	Panchakshari Gavayi Park								
		4	7.20	0.20	0.10	0.58			
		2	4.50	0.20	0.10	0.18			
	Vivekananda Park								
		4	4.90	0.20	0.10	0.39			
		1	5.70	0.20	0.10	0.11			
		1	4.50	0.20	0.10	0.09			
		1	5.40	0.20	0.10	0.11			
		3	5.10	0.20	0.10	0.31			
	CV Raman Park								
		5	5.80	0.20	0.10	0.58			
	Abdul Kalam Park								
		4	5.10	0.20	0.10	0.41			
		1	4.50	0.20	0.10	0.09			
	Visvesvaraya Park								
		13	5.50	0.20	0.10	1.43			
	Temple premises	1	5.10	0.20	0.10	0.10			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
		1	6.60	0.20	0.10	0.13			
		1	8.70	0.20	0.10	0.17			
	Dura Bendre Park								
		5	5.10	0.20	0.10	0.51			
	Ramana Maharshi Park								
		2	5.10	0.20	0.10	0.20			
		1	6.60	0.20	0.10	0.13			
	Kuvempu Park								
		9	7.70	0.20	0.10	1.39			
	CQAL Layout								
		10	6.80	0.20	0.10	1.36			
	Ward no 01								
	Anjaneya Swamy Temple Rd	1	2.10	0.20	0.10	0.04			
		2	1.20	0.20	0.10	0.05			
	Inside Post Office								
		1	12.50	0.20	0.10	0.25			
		1	1.80	0.20	0.10	0.04			
	Deduct Tree Guards	-2	0.60	0.20	0.10	-0.02			
		2	3.90	0.20	0.10	0.16			
		2	1.50	0.20	0.10	0.06			
		1	3.60	0.20	0.10	0.07			
		2	1.40	0.20	0.10	0.06			
	Inside Mini Vidhanasoudha								
	Infront Kempegowda Statue	4	4.30	0.20	0.10	0.34			
	Back Side Kempegowda Statue	2	4.30	0.20	0.10	0.17			
	Ashok Pillar Back Side	2	4.30	0.20	0.10	0.17			
	Infront of Ganesha Temple	2	3.50	0.20	0.10	0.14			
	Ambedkar Park								
	Northern Side	1	86.00	1.00	0.15	12.90			
	Eastern Side	1	13.50	1.00	0.15	2.03			
	Cobble Stone								
	Ambedkar Park								
	Eastern Side	1	84.30	2.35	0.15	29.72			
	Southern Side	1	98.00	2.50	0.15	36.75			
	Western Side	1	22.00	2.35	0.15	7.76			
	Northern Side	1	95.60	2.30	0.15	32.98			
	Concrete Road								
	Ch:30.00 to 36.90	1	36.90	8.50	0.130	40.77			
	Deduct								
	Room 1	-1	2.05	1.35	0.125	-0.35			
	Room 2	-1	2.05	2.05	0.125	-0.53			
	Room 3	-1	1.75	1.95	0.125	-0.43			
	Room 4	-1	1.70	1.70	0.125	-0.36			
	Right Side								
	Room 1	-1	1.95	1.95	0.125	-0.48			
	NIPCCD Staff Quarters(Blind School Park) Sand Filing Area								
		-1	3.20	3.70	0.30	-3.55			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
		-1	3.20	3.40	0.30	-3.26			
		-1	2.90	1.90	0.30	-1.65			
		-1	10.40	2.90	0.30	-9.05			
	New Kerb								
	Ambedkar Park								
	Eastern Side	1	115.90	0.20	0.10	2.32			
	NIPCCD Staff Quarters(Blind School Park)								
	Southern Side	1	36.90	0.20	0.10	0.74			
	Box-A								
		1	2.80	0.20	0.10	0.06			
		1	2.70	0.20	0.10	0.05			
	Box-B and Box-C								
		3	2.90	0.20	0.10	0.17			
		1	12.30	0.20	0.10	0.25			
	Box-D								
		2	3.70	0.20	0.10	0.15			
		1	3.20	0.20	0.10	0.06			
	Box-E								
		1	3.20	0.20	0.10	0.06			
		1	3.40	0.20	0.10	0.07			
		1	2.00	0.20	0.10	0.04			
	Ambedkar Park								
	Eastern Side LHS	1	84.30	0.20	0.10	1.69			
	Eastern Side RHS	1	81.90	0.20	0.10	1.64			
	Southern Side LHS	1	98.00	0.20	0.10	1.96			
	Southern Side RHS	1	95.50	0.20	0.10	1.91			
	Western Side LHS	1	22.00	0.20	0.10	0.44			
	Western Side RHS	1	22.00	0.20	0.10	0.44			
	Northern Side LHS	1	95.60	0.20	0.10	1.91			
	Northern Side RHS	1	93.30	0.20	0.10	1.87			
						449.60	Cum	5476.67	2462299.06
	Approved Rate	5476.67							
3	KSRB 5.2-3 Providing and constructing granite/ trap/ basalt size stone masonry in foundation with cement mortor 1:6, stone hammered dressed in course not less than 20cms high, bond stones at two m apart in each course including cost of materials, labour, curing complete as per specifications KBS5.1.13.								
	Sir M. Vishveshwaraya Park								
	South	1	48.80	0.75	0.70	25.62			
	West	1	83.10	0.75	0.80	49.86			
	North	1	84.90	0.75	0.80	50.94			
	East	1	69.50	0.75	0.80	41.70			
	In Between Fensing	1	49.00	0.75	0.80	29.40			
	Ambedkar Park								
	Northern Side	1	86.00	0.80	0.60	41.28			
	Eastern Side	1	13.50	0.80	0.60	6.48			
	Blind School								
	SSM For Compound Wall								
	Outside Wall	1	37.50	0.70	0.60	15.75			
	Inside Wall								
	Room 1	2	2.05	0.70	0.60	1.72			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Room 2	3	2.05	0.70	0.60	2.58			
	Room 3	2	1.75	0.70	0.60	1.47			
	Room 4	2	1.70	0.70	0.60	1.43			
	Right Side								
	Room 1	2	1.95	0.70	0.60	1.64			
	2nd Step								
	Sir M. Vishveshwaraya Park								
	South	1	43.90	0.60	0.53	14.01			
	West	1	83.10	0.60	0.60	29.92			
	North	1	79.20	0.60	0.50	23.76			
	East	1	69.50	0.60	0.60	25.02			
	In Between Fensing	1	49.00	0.60	0.40	11.76			
	Culvert	2	10.30	0.40	0.40	3.30			
	Ambedkar Park								
	Northern Side	1	86.00	0.60	0.60	30.96			
	Eastern Side	1	13.50	0.60	0.60	4.86			
						413.46	**Cum**		
			Upto 125%			**409.20**	**Cum**	**4920.97**	**2013660.92**
			Above 125%			**4.26**	**Cum**	**4920.97**	**20943.06**
	Approved Rate	4920.97							
4	KSRB 4-1.6; Providing and laying in positionplain cement concrete of mix 1:2:4 with opc @240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @0.53cum, machine mixed , concrete laid in layers not exceeding 15cms thick well compacted in foundation plinth and cills including cost of materials, labour, HOM curing complete as per specifications								
	Sir M. Vishveshwaraya Park								
	South	1	48.80	0.60	0.10	2.93			
	West	1	83.10	0.60	0.10	4.99			
	North	1	84.90	0.60	0.10	5.09			
	East	1	69.50	0.60	0.10	4.17			
	In Between Fensing	1	49.00	0.60	0.10	2.94			
	Culvert	2	10.30	0.40	0.08	0.66			
	Ambedkar Park								
	Northern Side	1	86.00	0.60	0.10	5.16			
	Eastern Side	1	13.50	0.60	0.10	0.81			
	Coping								
	Plinth For Compound Wall								
	Outside Wall	1	37.50	0.45	0.10	1.69			
	Inside Wall								
	Room 1	2	2.05	0.45	0.10	0.18			
	Room 2	3	2.05	0.45	0.10	0.28			
	Room 3	2	1.75	0.45	0.10	0.16			
	Room 4	2	1.70	0.45	0.10	0.15			
	Blind School								
	Solid Block For Compound Wall								
	Outside Wall	1	37.50	0.20	0.10	0.75			
	Inside Wall								
	Left Side								
	Room 1	2	2.05	0.20	0.10	0.08			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Room 2	3	2.05	0.20	0.10	0.12			
	Room 3	2	1.75	0.20	0.10	0.07			
	Room 4	2	1.70	0.20	0.10	0.07			
	Right Side								
	Room 1	2	1.95	0.20	0.10	0.08			
	Room 2 Area =5.1m	5.1		0.20	0.10	0.10			
	Deduct	-3	0.30	0.20	0.10	-0.02			
	Deduct	-1	2.90	0.20	0.10	-0.06			
	Deduct	-1	0.75	0.20	0.10	-0.02			
	Deduct	-7	0.40	0.20	0.10	-0.06			
						30.33	Cum		
			Upto 125%			27.26	Cum	5805.37	158268.90
			Above 125%			3.07	Cum	5805.37	17822.20
	Approved Rate	5805.37							
5	Fabricating, providing and erecting in position of MS hot dip galvonised Sq. Hallow Poles of 132x132 heavy guage of length 3000mm with MS. Hot dip galvonised grill work as per approved design and drawing of chief architect using 12x 75mm galvanised flat for alround frame and 20x20mm galvanised forged design with square for vertical at 150mm C/C as shown in the drawing including providing forged ornamental arrow head at top and bottom the work is inclusive of throughing flat square rods placing welding all the joints including grinding finishing 2 coats of anticorrosive paint over one coatof metal primer the rate is inclusive of all materials like MS hallow galvanized pipe flats forged square rods cost of								
	Sir M. Vishveshwaraya Park								
	South	1	43.90		1.80	79.02			
	West	1	83.10		1.80	149.58			
	North	1	79.20		1.80	142.56			
	East	1	69.50		1.80	125.10			
	In Between Fensing	1	49.00		1.80	88.20			
	Ambedkar Park								
	Northern Side	1	86.00		1.80	154.80			
	Eastern Side	1	13.50		1.80	24.30			
						763.56	Sqm	9236.35	7052507.41
	Approved Rate	9236.35							
6	Fabricating, providing and erecting in position of MS hot dip galvonised Gate. Using 72x72x4.8mm Sq GI pipe frame with top pipe bending with MS. Hot dip galvonised grill work as per approved design and drawing of chief architect using 75x12mm and 50x6mm Arch galvanised flat for alround frame and 20x20mm galvanised forged design with square for vertical at 150mm C/C as shown in the drawing								
	Sir M. Vishveshwaraya Park								
	Gates								
	Park Entrance	1.00	4.90		2.40	11.76			
	Temple	1.00	1.60		2.40	3.84			
	Temple Entrace	1.00	4.10		2.40	9.84			
						25.44	Sqm	12601.00	320569.44
	Approved Rate	12601.00							
7	providing and fixing Pre cast solid concrete kerb stones of size 450x200x400 mm made of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete as per direction of engineer incharge								
	Sir M. Vishveshwaraya Park								
	Missing Damaged Kerbs	1	71.00			71.00			
	Childrens Play Area	2	22.70			45.40			
	Benches Platform surround								
	Ward No:03								

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
Gunnapur Government school								
School Premises	1	28.80			28.80			
Attur								
Lake Premises	1	180.00			180.00			
Vishwanagar								
B Block	1	6.60			6.60			
1st cross road at dead end	1	7.90			7.90			
1st cross road	1	6.90			6.90			
2nd cross road	1	36.00			36.00			
Main Road near D Block	1	13.20			13.20			
Main Road near Karnataka pole	1	11.60			11.60			
HMS Extension								
1st cross road	1	27.00			27.00			
4th main road	1	4.30			4.30			
2nd main road	1	9.00			9.00			
Dasa Circle								
Near Help point	1	11.30			11.30			
Vidyaniki Park	1	130.70			130.70			
Kittur Rani Chennamma Park	1	72.00			72.00			
Sardar Vallabhai Patel Park	1	72.00			72.00			
BM Srikantaiah Park	1	74.40			74.40			
Panchakshari Gavayi Park	1	37.80			37.80			
Vivekananda Park	1	50.50			50.50			
CV Raman Park	1	29.00			29.00			
Abdul Kalam Park	1	24.90			24.90			
Visveswaraya Park	1	71.50			71.50			
Temple premises	1	20.40			20.40			
Dasa Bendre Park	1	25.50			25.50			
Ramana Maharshi Park	1	16.80			16.80			
Kuvempu Park	1	69.30			69.30			
Ward no 01								
Anjaneya Swamy Temple Rd	1	28.20			28.20			
Inside Mini Vidhanasoudha								
Infront Kempegowda Statue	4	4.30			17.20			
Back Side Kempegowda Statue	2	4.30			8.60			
Ashok Pillar Back Side	2	4.30			8.60			
Infront of Ganesha Temple	2	3.50			7.00			
New Kerb								
Ambedkar Park								
Eastern Side	1	115.90			115.90			
NIPCCD Staff Quarters(Blind School Park)								
Southern Side	1	36.90			36.90			
Box-A								
	1	2.80			2.80			
	1	2.70			2.70			
Box-B and Box-C								
	3	2.90			8.70			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
		1	12.30			12.30			
	Bus-D								
		2	3.70			7.40			
		1	3.20			3.20			
	Bus-E								
		1	3.20			3.20			
		1	3.40			3.40			
		1	2.00			2.00			
	Ambedkar Park								
	Eastern Side LHS								
		1	50.00			50.00			
	Eastern Side RHS								
		1	44.00			44.00			
	Southern Side LHS								
		1	59.00			59.00			
	Southern Side RHS								
		1	51.00			51.00			
	Western Side								
		2	22.00			44.00			
	Northern Side LHS								
		1	40.00			40.00			
	Northern Side RHS								
		1	68.00			68.00			
			\			1777.90			
						3951.00	**Nos**	**436.84**	**1725954.84**
	Approved Rate	436.84							
B	Painting two coats after filling the surface with synthentic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour completed as per specifications. Morth Chapter 8 specification No. KSRRB M800-6								
	Sir M. Vishveshwaraya Park								
	Missing Damaged Kerbs	1	71.00		0.30	21.30			
	Childrens Play Area	2	22.70		0.30	13.62			
	Benches Platform surround								
	Ward No:03								
	Anantapur Government school								
	School Premises	1	28.80		0.30	8.64			
	Attur								
	Lake Premises	1	180.00		0.30	54.00			
	Vishwanagar								
	B Block	1	0.00		0.30	0.00			
	1st cross road at dead end	1	0.00		0.30	0.00			
	1st cross road	1	0.00		0.30	0.00			
	2nd cross road	1	36.00		0.30	10.80			
	Main Road near D Block	1	13.20		0.30	3.96			
	Main Road near Karnataka pole	1	11.60		0.30	3.48			
	AMS Extension								
	1st cross road	1	27.00		0.30	8.10			
	4th main road	1	4.30		0.30	1.29			
	2nd main road	1	9.00		0.30	2.70			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Dairy Circle								
	Near Help point	1	11.30		0.30	3.39			
	Valmiki Park	1	83.00		0.30	24.90			
	Kittur Rani Chennamma Park	1	72.00		0.30	21.60			
	Sardar Vallabhai Patel Park	1	72.00		0.30	21.60			
	BM Srikantaiah Park	1	74.40		0.30	22.32			
	Panchakshari Gavayi Park	1	37.80		0.30	11.34			
	Vivekananda Park	1	50.50		0.30	15.15			
	CV Raman Park	1	29.00		0.30	8.70			
	Abdul Kalam Park	1	24.90		0.30	7.47			
	Visveswaraya Park	1	71.50		0.30	21.45			
	Temple premises	1	20.40		0.30	6.12			
	Dara Bendre Park	1	25.50		0.30	7.65			
	Ramana Maharshi Park	1	16.80		0.30	5.04			
	Kuvempu Park	1	69.30		0.30	20.79			
	Ward no 01								
	Anjaneya Swamy Temple Rd	1	5.00		0.30	1.50			
	Inside Mini Vidhanasoudha								
	Infront Kempegowda Statue	4	4.30		0.30	5.16			
	Back Side Kempegowda Statue	2	4.30		0.30	2.58			
	Ashok Pillar Back Side	2	4.30		0.30	2.58			
	Infront of Ganesha Temple	2	3.50		0.30	2.10			
	New Kerb								
	Ambedkar Park								
	Eastern Side	1	115.90		0.30	34.77			
	NIPCCD Staff Quarters(Blind School Park)								
	Southern Side	1	36.90		0.30	11.07			
	Box-A								
		1	2.80		0.30	0.84			
		1	2.70		0.30	0.81			
	Box-B and Box-C								
		3	2.90		0.30	2.61			
		1	12.30		0.30	3.69			
	Box-D								
		2	3.70		0.30	2.22			
		1	3.20		0.30	0.96			
	Box-E								
		1	3.20		0.30	0.96			
		1	3.40		0.30	1.02			
		1	2.00		0.30	0.60			
	Ambedkar Park								
	Eastern Side LHS	1	84.30		0.30	25.29			
	Eastern Side RHS	1	81.90		0.30	24.57			
	Southern Side LHS	1	98.00		0.30	29.40			
	Southern Side RHS	1	95.50		0.30	28.65			
	Western Side LHS	1	22.00		0.30	6.60			
	Western Side RHS	1	22.00		0.30	6.60			
	Northern Side LHS	1	95.60		0.30	28.68			
	Northern Side RHS	1	93.30		0.30	27.99			

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
					576.66	Sqm	85.66	49396.70
Approved Rate	85.66							
Providing and laying / fixing cement base precast pre polished cement concrete designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring treads of steps and landing, laid on a bed of 12mm thick cement mortor 1:3 mis finished eith flush pointing using white cement includingcost of materials mortor including cutting grinding the edge to half/full round wherever required labou curing complete as per specifications.								
Benches Platform								
Ward No:03								
Dhoo Marvel Layout								
Near Main Gate	1	2.10	1.50		3.15			
Layout Association	3	2.10	1.50		9.45			
1st Cross (Opp Kempton Appt)	2	2.10	1.20		5.04			
Opp Kempegowda Hall	4	2.10	1.20		10.08			
Near Vinayaka Temple	4	2.10	1.20		10.08			
Park	10	2.10	1.50		31.50			
Ramnagar Government school								
School Premises	2	5.20	1.50		15.60			
Attur								
Lake Premises	25	2.10	1.50		78.75			
Yelahwanagar								
B Block	1	1.80	1.50		2.70			
1st cross road at dead end	1	1.95	2.00		3.90			
1st cross road	1	2.00	1.45		2.90			
2nd cross road	6	1.80	1.20		12.96			
Main Road near D Block	2	1.80	1.50		5.40			
Main Road near Karnataka pole	2	1.80	1.10		3.96			
ADB Extension								
1st cross road	6	2.10	1.20		15.12			
4th main road	1	2.10	1.10		2.31			
2nd main road	2	2.10	1.20		5.04			
Gaon Circle								
Near Help point	1	1.80	1.40		2.52			
	1	2.60	0.90		2.34			
Valmiki Park								
	3	2.10	1.30		8.19			
	1	2.10	1.40		2.94			
	2	2.10	1.50		6.30			
	1	2.10	1.20		2.52			
	1	2.10	1.35		2.84			
	2	2.10	1.50		6.30			
	10	1.80	1.60		28.80			
Kittur Rani Chennamma Park								
	10	2.10	1.50		31.50			
Sardar Vallabhai Patel Park								
	10	2.10	1.50		31.50			
BM Srikantaiah Park								
	8	2.10	1.50		25.20			

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	2	2.10	2.10		8.82			
Panchakshari Gavayi Park								
	4	2.10	1.50		12.60			
	2	2.10	1.20		5.04			
Vivekananda Park								
	4	2.10	1.40		11.76			
	1	2.10	1.80		3.78			
	1	2.10	1.20		2.52			
	1	2.10	1.65		3.47			
	3	2.10	1.50		9.45			
CV Raman Park								
	5	2.10	1.50		15.75			
Abdul Kalam Park								
	4	2.10	1.50		12.60			
	1	2.10	1.20		2.52			
Visvesvaraya Park								
	3	2.10	1.40		8.82			
	3	1.80	1.60		8.64			
	4	2.10	1.50		12.60			
	1	2.10	1.90		3.99			
	1	2.10	1.70		3.57			
	1	2.10	1.85		3.89			
Temple premises	1	2.10	1.50		3.15			
	1	3.60	1.50		5.40			
	1	5.70	1.50		8.55			
Dara Bendre Park								
	4	2.10	1.50		12.60			
	1	2.10	1.50		3.15			
Ramana Maharshi Park								
	2	2.10	1.50		6.30			
	1	3.60	1.50		5.40			
Kuvempu Park								
	7	2.30	1.55		24.96			
	2	2.00	1.65		6.60			
Ward no 01								
Maruthinagara								
Opp To BWSSB	1	4.70	1.20		5.64			
	8	2.10	1.20		20.16			
Near BWSSB	1	3.60	1.50		5.40			
Maruthi Nagara 2nd Stage	2	2.10	1.20		5.04			
	1	3.60	1.20		4.32			
	4	2.10	1.20		10.08			
Vikas Layout								
1st Main Rd	3	2.10	1.20		7.56			
3rd Main Rd	4	2.10	1.20		10.08			
3rd Cross Rd	4	2.10	1.20		10.08			
2nd Cross Rd	4	2.10	1.20		10.08			
Main Road	5	2.10	1.20		12.60			
2nd Cross Rd(Vivekanda Rd)	3	2.10	1.20		7.56			
	2	5.40	1.20		12.96			

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
Main Rd Upto 4th Cross Rd	3	2.10	1.20		7.56			
Cross Rd	2	2.10	1.20		5.04			
4th Cross Rd	1	3.60	1.20		4.32			
Bailuri Layout								
Main Road	5	2.10	1.20		12.60			
3rd Cross Rd LHS Side	4	2.10	1.20		10.08			
3rd Cross Rd RHS Side	7	2.10	1.20		17.64			
Near School Rd	2	2.10	1.20		5.04			
Ward Member Vishwa House	2	2.10	1.20		5.04			
Near Cambridge School (SIR-M-V Rd)	3	2.10	1.20		7.56			
Cross Rd	1	2.10	1.20		2.52			
Cross Rd-1	2	2.10	1.20		5.04			
Shivanahalli (Jakkur Layout)								
	1	3.60	1.20		4.32			
Shivanahalli Main Rd								
	1	2.10	1.40		2.94			
	2	2.10	1.20		5.04			
Cross Rd-2	2	2.10	1.20		5.04			
Cricket Club Rd	1	3.60	1.20		4.32			
Anjaneya Swamy Temple Rd	4	2.10	1.20		10.08			
Krushi University Employee Union Rd	3	3.60	1.20		12.96			
Sky Blue Appartment	2	2.10	1.20		5.04			
Sri Nikethana #133	2	3.60	1.20		8.64			
Inside Post Office								
	1	12.50	1.80		22.50			
Deduct Tree Guards	-2	0.60	0.60		-0.72			
	1	3.90	1.50		5.85			
	1	3.60	1.40		5.04			
Inside Mini Vidhanasoudha								
Infront Kempegowda Statue	4	2.50	1.80		18.00			
Back Side Kempegowda Statue	2	2.50	1.80		9.00			
Ashok Pillar Back Side	2	2.50	1.80		9.00			
Infront of Ganesha Temple	2	2.15	1.65		7.10			
					912.95	**Sqm**	**1319.11**	**1204274.88**
Approved Rate	1319.11							
KSHRB M300-53 Construction of embankment with approved materials Gravel/Murrum with all lifts and leads, transportating to site, spreading grading to required slopes and compacting to meet required table 300-2 complete as per specification including cost of gravel/ murrum watering charges and compaction by vibratory roller to 95% of modified proctors density MORTH specification No.305								
Benches Platform								
Ward No:03								
Duo Marvel Layout								
Near Main Gate	1	2.10	1.50	0.15	0.47			
Layout Association	3	2.10	1.50	0.15	1.42			
1st Cross (Opp Kempton Appt)	2	2.10	1.20	0.15	0.76			

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
Near Kempegowda Hall	4	2.10	1.20	0.15	1.51			
Near Vinayaka Temple	4	2.10	1.20	0.15	1.51			
Park	10	2.10	1.50	0.15	4.73			
Anantapur Government school								
School Premises	2	5.20	1.50	0.15	2.34			
Attur								
Lake Premises	22	2.10	1.50	0.15	10.40			
Vishwanagar								
B Block	1	1.80	1.50	0.15	0.41			
1st cross road at dead end	1	1.95	2.00	0.15	0.59			
1st cross road	1	2.00	1.45	0.15	0.44			
2nd cross road	6	1.80	1.20	0.15	1.94			
Main Road near D Block	2	1.80	1.50	0.15	0.81			
Main Road near Karnataka pole	2	1.80	1.10	0.15	0.59			
AIMS Extension								
1st cross road	6	2.10	1.20	0.15	2.27			
4th main road	1	2.10	1.10	0.15	0.35			
2nd main road	2	2.10	1.20	0.15	0.76			
Near Karnataka pole	1	0.00	0.00	0.15	0.00			
Dairy Circle								
Near Help point	1	1.80	1.40	0.15	0.38			
	1	2.60	0.90	0.15	0.35			
Valmiki Park								
	3	2.10	1.30	0.15	1.23			
	1	2.10	1.40	0.15	0.44			
	2	2.10	1.50	0.15	0.95			
	1	2.10	1.20	0.15	0.38			
	1	2.10	1.35	0.15	0.43			
	2	2.10	1.50	0.15	0.95			
Kittur Rani Chennamma Park								
	10	2.10	1.50	0.15	4.73			
Sardar Vallabhai Patel Park								
	10	2.10	1.50	0.15	4.73			
BM Srikantaiah Park								
	8	2.10	1.50	0.15	3.78			
	2	2.10	2.10	0.15	1.32			
Panchakshari Gavayi Park								
	4	2.10	1.50	0.15	1.89			
	2	2.10	1.20	0.15	0.76			
Vivekananda Park								
	4	2.10	1.40	0.15	1.76			
	1	2.10	1.80	0.15	0.57			
	1	2.10	1.20	0.15	0.38			
	1	2.10	1.65	0.15	0.52			
	3	2.10	1.50	0.15	1.42			
CV Raman Park								
	5	2.10	1.50	0.15	2.36			
Abdul Kalam Park								

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	4	2.10	1.50	0.15	1.89			
	1	2.10	1.20	0.15	0.38			
Visveswaraya Park								
	3	2.10	1.40	0.15	1.32			
	4	2.10	1.50	0.15	1.89			
	1	2.10	1.90	0.15	0.60			
	1	2.10	1.70	0.15	0.54			
	1	2.10	1.85	0.15	0.58			
Temple premises	1	2.10	1.50	0.15	0.47			
	1	3.60	1.50	0.15	0.81			
	1	5.70	1.50	0.15	1.28			
Dara Bendre Park								
	4	2.10	1.50	0.15	1.89			
	1	2.10	1.50	0.15	0.47			
Ramana Maharshi Park								
	2	2.10	1.50	0.15	0.95			
	1	3.60	1.50	0.15	0.81			
Kuvempu Park								
	7	2.30	1.55	0.15	3.74			
	2	2.00	1.65	0.15	0.99			
For Levelling								
Ambedkar Park								
	1	30.00	7.00	0.40	84.00			
	1	30.00	6.80	0.30	61.20			
	1	30.00	6.50	0.30	58.50			
	1	25.40	6.20	0.30	47.24			
NIPCCD Staff Quarters(Blind School Park) Inner Play Area								
	1	30.00	8.20	0.45	110.70			
	1	7.00	8.10	0.45	25.52			
NIPCCD Staff Quarters(Blind School Park) Outer								
	1	30.00	5.50	0.30	49.50			
	1	7.00	5.40	0.30	11.34			
					527.19	Cum	**347.98**	**183450.01**
Approved Rate	347.98							
2.6 Providing and filling sand in trenches to required depth including watering rammering with all the leads and lift complete as per specifications and direction by the engineer incharge at the site								
Sir M. Vishveshwaraya Park								
Childrens Play Area	1	8.20	14.50	0.30	35.67			
Panchakshari Gavayi Park								
Childrens Play Area	1	10.00	10.90	0.30	32.70			
Vivekananda Park								
Childrens Play Area	1	26.20	10.00	0.30	78.60			
Sardar Vallabhai Patel Park								
Childrens Play Area	1	20.20	14.50	0.30	87.87			
NIPCCD Staff Quarters(Blind School Park)								
	1	3.20	3.70	0.30	3.55			

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	1	3.20	3.40	0.30	3.26			
	1	2.90	1.90	0.30	1.65			
	1	10.40	2.90	0.30	9.05			
					252.36	**Cum**	**2205.65**	**556611.22**
Approved Rate	2205.65							
KSRB 14.6: Providing and laying heavy duty cobble stones inter lock pavers using cement and course sand for manufacture of blocks of approved size shape and colour with minimum compressive strength of 280kg per Sqm over 50mm thick sand bed and compacting with plate vibrator having 3tons compaction force there by forcing part of sand underneath to come up in between joints final compaction of pavers surface joints into its final including cost of materials labours and HOM complete								
Sir M. Vishveshwaraya Park								
Southern Side	1	37.10	3.65		135.42			
Pathway of Park Premises	1	52.00	3.00		156.00			
Inside Mini Vidhanasoudha								
Parking Area	1	38.40	12.90		495.36			
Pathway-Left hand Side	1	66.50	1.70		113.05			
Pathway-Right hand Side	1	41.50	1.60		66.40			
Building Front	1	24.90	1.55		38.60			
Entrance Main Gate	1	13.50	10.30		139.05			
2nd Part Bill								
Ambedkar Park								
Eastern Side								
	1	45.00	2.35		105.75			
Southern Side								
	1	25.00	2.61		65.25			
Western Side								
	1	22.00	2.35		51.70			
Northern Side								
	1	27.00	2.30		62.10			
					1428.67	**Sqm**	**1127.45**	**1610753.99**
Approved Rate	1127.45							
Executive Bench-Made out of Sadarahalli grey stone with hanmd supportys with 3 line finishing with arch design with 100mm slabs.Height 90x Length 1500 width 45cms.								
Benches								
Ward No:03								
Duo Marvel Layout								
Near Main Gate	1				1.00			
Layout Association	3				3.00			
1st Cross (Opp Kempton Appt)	2				2.00			
Opp Kempegowda Hall	4				4.00			
Near Vinayaka Temple	4				4.00			
Park	10				10.00			
Anantapur Government school								
School Premises	6				6.00			
Kempaiah Building	1				1.00			
Attur								
Lake Premises	25				25.00			
Vishwanagar								
B Block	1				1.00			